

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name H. Tiepermann "A" Well No. # 2

Location C S/2 SW SE Sec. 6 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3673'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:15 PM Day 7th Month Feb. Year 1966

The Above well was plugged as follows:

221' of 10 3/4" surface pipe, cemented with 275 sacks. 3667' of 7" long string, cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded to 3650', and cemented with 5 sacks, through the dump bailer. 1658' of 7" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 220', rock bridge from 220' to 210'. 5 sacks of cement was mixed in barrel, and put on plug at 210', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and hole was filled with 4 1/2 yards of ready-mix cement from 200' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/8/66
INV. NO. 2702-w