

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Sept. 1, 1966.

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bld'g. Wichita, Kansas

Lease Name Elsen Well No. #1

Location SE-NE-NW Sec. 6 Twp. 22 Rge. 12 (E) (W) X

County Stafford Total Depth 3655'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 950, Eldorado, Kansas License No. 547

Operation Completed: Hour 4:30 PM Day 1 Month 9 Year 1966

The Above well was plugged as follows:

346' of 8 5/8" surface pipe cemented with 1250 sacks. 3655' of 5 1/2" long
string cemented with 100 sacks. plug back to 3570'. Top perf. 3426'
Sand to 3400' & 5 sacks cement. Mud to 3300'. 15' rock bridge & 25 sacks
cement. Mud to 40', 10' rock bridge & 10 sacks cement to bottom of collar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: W. H. Justice
Well Plugging Supervisor

INVOICED

SEP 6 1966

DATE 9/6/66

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 3866-4