

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Western Petroleum Inc.

Complete Address: 925 Patton, Great Bend, Kansas

Lease Name Charles Well No. # 1

Location SE SE NE Sec. 6 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3672

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 9:00AM Day 10th Month June Year 1963

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cement circulated with 250 sacks. 3667' of
5 1/2" long string, cemented with 50 sacks. Sanded to 3650', cemented with
5 sacks. Fluid level was up in hole. Plug was set at 225', 10' rock bridge,
5 sacks cement was mixed and put on plug through dump bailer and let set
over night. Next morning hole bailed down and 15 sacks was added to plug.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar.

3100' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Arlene Elving
Well Plugging Supervisor

INVOICED

DATE 6/12/63

INV. NO. 7249 W