

15.185-19411-0000

Form CP-3
Rev. 6-26-62

15
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name R. P. Nixon Operations, Inc.

Complete Address: 754 East Wichita Ave., Russell, Kansas

Lease Name Blackburn Well No. # 1

Location SW NW NE Sec. 6 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3665

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Shields Drilling Company Inc.

Address: Shields Bldg., Russell, Kansas License No.

Operation Completed: Hour 11:00PM Day 10th Month Nov. Year 1964

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated with 255 sacks. Fluid
in the hole was at a 165' level. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 230', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/13/64

INV. NO. 144-W

Signed: Archie Elving
Well Plugging Supervisor