

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1967
5-19-67
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued May 1, 1967.Operator's Full Name Circle Oil Company, Inc.Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202Lease Name Tieperman "B" Well No. # 1Location NW NW SE Sec. 6 Twp. 22 Rge. 12 (E) (W)WCounty Stafford Total Depth 3427'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.Address: Box 221, Great Bend, Kansas 67530 License No. 49Operation Completed: Hour 11:00AM Day 18th Month May Year 1967

The Above well was plugged as follows:

315' of 8 5/8" surface pipe, cement circulated. 3356' of 5 1/2" long string,
cemented with 100 sacks. Top perforation 3340'. Bottom of the hole was sanded
to 3300', and cemented with 5 sacks, through the dump bailer. 2810' of 5 1/2" long
string was recovered from the hole. Bridge plug was pushed in fluid to 300',
bridge plug and rock bridge from 300' to 290'. 10 sacks of cement was mixed in
a barrel, and put on plug at 290', through the dump bailer, and let set over-
night. Next day hole was bailed dry, and 15 sacks of cement was added to the
plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 5/19/67
INV. NO. 5249-W