

KANSAS

*10*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 7 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed July 25, 1967.

Operator's Full Name Petroleum, Inc.

Complete Address 300 West Douglas, Wichita, Kansas 67202

Lease Name Unruh Well No. # 3

Location NW SW SE Sec. 8 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3925'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Garvey Drilling Company

Address R. R. # 2, Great Bend, Kansas 67530 License No.     

Operation Completed: Hour 9:45 P.M. Day 3rd Month August Year 1967

The above well was plugged as follows:

292' of 8 5/8" surface pipe, cemented with 252 sacks. Fluid level in  
the hole was at 50'. 50 sacks of cement was spotted through the drill  
pipe at 400'. Hole was filled with drilling mud to 40', plug bridged  
with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks from  
30' to the base of the cellar.

This cementing was done by Globe Cementing Company

These plugging orders were given by W. L. Nichols, Morland, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving  
Well Plugging Supervisor

INVOICED

DATE 8/8/67  
INV. NO. 6090-W