

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 11 1964
8-11-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.
Complete Address: Route 2, Great Bend, Kansas
Lease Name Unruh Well No. # 1
Location SW NE SE Sec. 8 Twp. 22 Rge. 14 (E) (W)
County Stafford Total Depth 3915
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Southwest Casing Pulling Co.
Address: Box 364, Great Bend, Kansas License No. 399
Operation Completed: Hour 11:00AM Day 10th Month August Year 1964

The Above well was plugged as follows:

223' of 8 5/8" surface pipe, cemented with 175 sacks. 3914' of 5 1/2" long
string, cemented with 100 sacks. Plug back to 3690'. Top perforation
3599'. Bottom of the hole was sanded to 3580', and cemented with 5 sacks.
Hole was flowing with water, and a squeeze job was necessary. 10 sacks
of Gel-Mud and 70 sacks of cement was pumped into surface pipe, through
an 8 5/8" swage, to a pressure of 200 lbs. A wiping plug was run between
the Gel-Mud and the cement. This cementing was done by Southwest Casing
pulling Co. 5 sacks of cement was used to cap off hole to the base of the
cellar. 2800' of 5 1/2" long string was recovered from the hole.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/11/64

INV. NO. 9634-W