

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 70-14

LOCATION 71/2-SW

SEC. 12 TWP. 22 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Drach

Operator Walker Drilling Co Address 7923 E. 4<sup>th</sup> St - Hutchinson - Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3696 Feet. 11

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 237 ft. Circulated with Cement -  
4 1/2 sacks set at 3689 ft - 15 sacks of cement  
dumped on bottom of hole - Shut off & Pulled 4 1/2  
again - Filled with mud to 240 ft - Put Bridge & 20  
sacks of cement at 240 ft - Mud to 20 ft. Plug & 10 sacks  
of cement at the surface  
Walker Drilling Co - Plugging - Contractor

E. M. Storch  
District Conservation Agent

Date 12-14-48

**PLUGGING**  
FILE SEC 17-22-R-13W  
BOOK PAGE 70 LINE 14

12-16-48