

KANSAS

AL STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1972
CONSERVATION DIVISION
Wichita, Kansas
4-13-72

Operator's Full Name Clinton Oil Co.

Complete Address 217 N Water Wichita, Ks

Lease Name Walter Scheib Well No. 2

Location E/2 SW/SE Sec 12 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3685

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 3:00 PM Day 11 Month 4 Year 1972

The above well was plugged as follows:

239 ft 8 5/8 surface pipe cemented with 150 sacks. 3677 ft 5 1/2 long
string cemented with 100 sacks. Open hole. Sand back to 3650 ft,
5 sacks cement with bailer. Pulled 1800 ft 5 1/2. Set 10 ft rock bridge
at 260 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. Russell Schuster*
Well Plugging Supervisor

DATE 4/13/72

INV. NO. 5549-W