

KANSAS

*SP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name R. W. Lange

Complete Address Box 1034, Garden City, Kansas

Lease Name Miller Well No. 1

Location NW SE Sec. 21 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4490'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated None

Plugging Contractor Knight Casing Pulling Co.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 11:30AM Day 21 Month 4 Year 1971

The above well was plugged as follows:

8 5/8" to 282' circulated w/ cement. 5 1/2" to 4490' cemented.

Top perforations 4428' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4350' Mud 4350' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 280'

Spotted 30 sacks cement 280' to 180' Mud 180' to 40'

Plug. Hulls & 10 sacks cement 40' to 0'. Allied Pump Truck

Pulled 2830' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves  
Well Plugging Supervisor

INVOICED

DATE 4/29/71  
INV. NO. 3602-W