

State of Kansas



15-185-11426-0001

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 12, 1968.

Dear Sir:

Mr. Clarence Michael of Sage Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name: Leonard Voigt "C" Well No. # 1

Location: SE SW SE Sec. 11 Twp. 22 Rge. 12 (E)(W) W

County Stafford Total Depth 3683' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

214' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar, Bridge and cement rat hole with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1968
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Arlene Elving
Conservation Division Agent