

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-185-19413-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Inc.

Complete Address: 925 Patton, Great Bend, Kansas

Lease Name: Charles Well No. # 1

Location: SE SE NE Sec. 6 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3672 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

256' of 8 5/8" surface pipe, cement circulated with 250
sacks. 3667' of 5 1/2" long string, cemented with 50 sacks.
Sand to 3650', cement with 5 sacks. Fill hole with mud to
225', 10' rock bridge, cement with 20 sacks. Mud to 40',
10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent