



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B & B Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: JA Allison & Algar Resources

Complete Address: 1415 Wichita Plaza Wichita, Ks

Lease Name: Brining Well No. 1

Location: C E/2 NW/SW Sec. 11 Twp. 22S Rge. 14 (E)(W) W

County: Stafford Total Depth 3794 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

326 ft 8 5/8 surface pipe cemented with 275 sacks. Pump

40 sacks cement to 600 ft. 2nd plug at 300 ft with 25

sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks

cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent