

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-185-12004-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1963

10-23-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Duke Burt of Duke Burt Drilling Co. has this date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: Fred Shaffer

Complete Address: Walcott Bldg., Hutchinson, Kansas

Lease Name: Teichmann Well No. # 1

Location: SE SE SE Sec. 12 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3686 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burt was instructed to plug the well as follows:

258' of 8 5/8" surface pipe, cemented with 250 sacks.

Fill hole with drilling mud to 250', 1st cementing plug,

1/4 sack hulls, cement with 25 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement

with 15 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent