

KANSAS

FORM CP-3
Rev, 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-185-01251-0001

245 North Water
Wichita, KS 67202

Operator's Full Name Kelso Casing Pulling

Complete Address P. O. Box 176, Chase, Kansas 67524

Lease Name Spangenburg Well No. 1

Location NW NW SE Sec. 16 Twp. 22S Rge. 12 (~~EAST~~) (West)

County Stafford Total Depth 3735'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4:00 Day 3 Month 12 Year 1980
PM

The above well was plugged as follows:

Pumped 35 sx cement and pushed plug to 3300'.

Squeezed thru 8 5/8" surface casing with 4 sx hulls, 25 sx mud-gel, 1 sx hulls, plug, and 100 sx cement.

Max. pres. 100#. Shut in pres. 50#.

Recovered approx. 2812' of 4 1/2" casing.

Plugged back to 3670'. Top perforation at 3442'.

3735' of 4 1/2" casing.

240' of 8 5/8" surface casing cement circ.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 5 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Deane Rankin
Conservation Division Agent

INVOICED

DATE 12-8-80

INV. NO. 3704-W