

KANSAS


 STATE CORPORATION COMMISSION

 CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
 STATE CORPORATION COMMISSION

 J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

 MAY 14 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

 Operator's Full Name Clinton Oil Co.  
 Complete Address 217 N. Water Wichita, Ks  
 Lease Name K.E. Horyna Well No. 1-V  
 Location NE/NE/SW Sec. 16 Twp. 22 Rge. 12 (E) (W)<sup>W</sup>  
 County Stafford Total Depth 3705  
 Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
 Other well as hereafter indicated \_\_\_\_\_  
 Plugging Contractor Knight Casing Pulling Co. Inc.  
 Address Box 405 Chase, Ks License No. 436  
 Operation Completed: Hour 4:00 PM Day 12 Month 5 Year 1971

The above well was plugged as follows:

288 ft of 8 5/8 surface pipe cemented with 225 sacks. 3702 ft of 5 1/2  
long string cemented with 150 sacks. Open hole. Sand back to 3690  
ft, 5 sacks cement with bailer. Pulled 2700 ft of 5 1/2. Pumped 2  
sacks hulls, 15 sacks gel., 100 sacks cement to surface.
Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

 DATE 5/14/71

 INV. NO. 3702-W

 Signed: A. Russell Bunker  
 Well Plugging Supervisor