

15-185-01396-0001

Form CP-3
Rev. 6-4-68

KANSAS

J
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Harry Sprague

Complete Address Box 348 McPherson, Ks

Lease Name Long Well No. 1

Location NW/SW/NE Sec. 2- Twp. 23 Rge. 13 (E) (W)

County Stafford Total Depth 3870

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King Hutchinson, Ks License No. 440

Operation Completed: Hour 5:30 PM Day 28 Month 8 Year 1970

The above well was plugged as follows:

172 ft of 8 5/8 surface pipe cemented with 450 sacks. 3866 ft of

5 1/2 long string cemented with 150 sacks. Top perf. 3472 ft. Sand

back to 3450 ft, 5 sacks cement with bailer. Pulled 2950 ft of 5 1/2.

Pumped 15 sacks gel & 100 sacks cement to surface.

Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: G Russell Bilstein
Well Plugging Supervisor

DATE 9/1/70

INV. NO. 2455-W