

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Glen N. Rupe 15-185-20424-0000

Complete Address Suite 940 200 W Douglas Wichita, Ks

Lease Name Scheib Well No. 1

Location NE/SE/SW Sec. 4 Twp. 23 Rge. 13 (E) (W)

County Stafford Total Depth 3870

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Inc

Address Box 698 Great Bend, Ks License No. 637

Operation Completed: Hour 3:00 PM Day 11 Month 11 Year 1972

The above well was plugged as follows:

268 ft 8 5/8 surface pipe cemented with 275 sacks. 3867 ft 5 1/2 long

string cemented with 150 sacks. Top perf. 3519 ft. Sand to 3470 ft,

5 sacks cement with bailer. Pulled 2900 ft 5 1/2. Pump 2 sacks hulls,

15 sacks gel, 100 sacks cement to surface.

Pumped by Sun Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/13/72

INV. NO. 6626-U