

KANSAS
STATE CORPORATION COMMISSION

15-185-01386-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DEC - 6 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Jay Kornfeld

Complete Address: 623 Union National Bldg., Wichita, Kansas

Lease Name Metz Well No. # 1

Location NE SW SW Sec. 4 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3876'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30 PM Day 5th Month Dec. Year 1965

The Above well was plugged as follows:

365' of 8 5/8" surface pipe, cement circulated. 3876' of 5 1/2" long
string, cemented with 100 sacks. Plug back to 3604'. Plug was pushed
to 3500', and 50' of sand, and cemented with 5 sacks. 2756' of 5 1/2"
long string was recovered from the hole. Fluid in the hole was bailed
down to 200', rock bridge from 200' to 190', and cemented with 25
sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/6/65
INV. NO. 2340-W