

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-185-30240-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

APR 11 1966

CONSERVATION DIVISION  
Wichita, Kansas

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ, Commissioner  
HARRY G. WILES, Commissioner  
RAYMOND B. HARVEY, Secretary  
ROBT. C. LONDERHOLM, Gen. Counsel

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling Co., Inc has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips-Graves Drilling Company, Inc.

Complete Address: 412 Union Center Bldg., Wichita, Kansas

Lease Name: Emilie Fischer Well No. # 1

Location: NW SE SW Sec. 5 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3260' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

252' of 8 5/8" surface pipe, cement circulated with 250 sacks.

Fill hole with drilling mud to 240', 1st cementing plug, bridge

with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement

with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent