

15-009-05534-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 23-5

LOCATION Swe - NE 1/4

SEC. 34 TWP. 16 RGE. 11-w

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 8 Lease Frees - "A"

Operator El Morado Refining Co Address Box #209 Russell-Kans

Field _____ County Barton

Total Depth 3408 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" - 320ft Circulated with cement.
5 1/2" casing set at 3309ft - Heavy mud to 3000ft.
Set Rock Bridge & dumped 5 sacks of cement at 3000ft.
Ripped off & pulled the 5 1/2" casing - Filled with mud to
320ft - Set Rock Bridge & 15 sacks of cement at 320ft.
Mud to 30ft - Bridge & 10 sacks of cement
at the surface

Skull Packing Pulling Co - Plugging Contractors

SEP 11 1950 9-11-50

STATE CORPORATION

C. R. Stough

District Conservation Agent

Date 9-9-50

PLUGGING
FILE SEC 34 T 16 R 11w
BOOK PAGE 23 LINE 5