

15009-20610-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Oil Company
Complete Address 200 W. Douglas, Suit 550,
Wichita, Kansas 67202

Lease Name Homolka Well No. # 1

Location SE NE NE Sec. 35 Twp. 16 Rge. 11 (E) (W) W

County Barton Total Depth 3390

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address 1720 Wichita Plaza, Wichita, Kansas Sense No.
67202

Operation Completed: Hour 9:15 A.M Day 15 Month 8 Year 1971

The above well was plugged as follows:

8 5/8" csg. 237' Cwc.
Circulated hole with heavy mud to 500', set plug, & displaced 50 sax cement thru
drill pipe. Mud to 230' & displaced 25 sax cement thru drill pipe. Mud to 40',
1/2 sax hulls, plug, & displaced 10 sax cement with Halliburton Cementing Company's
pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/18/71
INV. NO. 4160-W

Signed: [Signature]
Well Plugging Supervisor