



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kelso of R. W. Lange has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: R.W. Lange

Complete Address: Box 1034, Garden City, Kansas

Lease Name: Miller Well No. 2

Location: NE SE Sec. 21 Twp. 22 Rge. 22 ~~(E)~~ (W)

County: Hodgeman Total Depth 4440' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kelso was instructed to plug the well as follows:

8 5/8" to 272' circulated w/ cement. 5 1/2" to 4426' cemented.

Open hole 4426' to 4440' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4350' Mud 4350' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 270'

Spot 30 sacks cement 270' to 170' Mud 170' to 40'

Plug, H₁₁ls @ 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent