



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 31 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Reeves of Aspen Drlg. Co. Inc has this  
date requested permission to plug the following described well:

Mr. Reeves guarantees payment of the plugging fee.

Operator's full Name: Aspen Resources Ltd.

Complete Address: Box 783 Broadway at Morton Great Bend, Ks

Lease Name: Gartung Well No. 4

Location: SW/SE/NW/NW Sec. 4 Twp. 22s Rge. 14 (E)(W)W

County: Stafford Total Depth 3955 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Reeves was instructed to plug the well as follows:

450 ft of 8 5/8 surface pipe cemented with 325 sacks.

Fill hole to 420 ft, plug, 1/2 sack hulls, 25 sacks cement.

Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to

surface. 2 sacks cement in rat hole.

Very truly yours,

N. Russell Bihunter  
Conservation Division Agent