



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Reed of Aspen Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Reed guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Co.

Complete Address: 117 Cameron Bldg. Oklahoma City, OK

Lease Name: Unruh Well No. 2

Location: NE/SW/SW Sec. 4 Twp. 22s Rge. 14 (E)(W) W

County: Stafford Total Depth 3875 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reed was instructed to plug the well as follows:

454 ft of 8 5/8 surface pipe cemented with 375 sacks. Bottom
plug at 650 ft with 40 sacks cement. Second plug at 400 ft,
with 25 sacks cement. Mud to 40 ft, plug, 1/2 sack hulls,
10 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

A. Russell Biberstein
Conservation Division Agent