

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-185-00570-0001

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
MONT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. L. C. Brau of Edmiston Drilling Co. has this

date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Ks.

Lease Name: Cassady Well No. # 1-A

Location: NE NE NW Sec. 16 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3844 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

300' of 8 5/8" surface pipe, cemented with 250 sacks. Fill
hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving

Conservation Division Agent