

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

STATE CORPORATION COMMISSION

FEB 16 1995 2-16-95

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and FILE ONE COPY)

API # 15-055-21,378-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Lebsack Oil Production, Inc. KCC LICENSE # 5210 ^{6/95}
(owner/company name) (operator's)

ADDRESS P.O. Box 489 CITY Hays

STATE Kansas ZIP CODE 67601 CONTACT PHONE # (913) 625-5444

LEASE Garden City "D" WELL# 1-18 SEC. 18 T. 22S R. 33 ~~XXXX~~ (West)

- NE - NE - SE SPOT LOCATION/QQQQ COUNTY Finney

2310 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

CHECK ONE: OIL WELL GAS WELL D&A SWD/ENGR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 251.10 CEMENTED WITH 100 SACKS

PRODUCTION CASING SIZE SET AT CEMENTED WITH SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:

ELEVATION 2895/2900' T.D. 4840' PERD ANHYDRITE DEPTH
(G.L./R.E.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill with heavy mud; 1st plug @ 3500' with 100 sks., 2nd plug @ 2005' with 50 sks., 3rd plug @ 1100' with 80 sks., 4th plug @ 600' with 40 sks., 5th plug @ 290' with 50 sks., 6th plug @ 40' with 10 sks., 15 sks rathole, total 345 sks 60/40 pos,
(if additional space is needed attach separate page)
6% gel, with 1/4# floeal per sk.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACC-1 FILED?

If not explain why? Sent to operator

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# (316) 262-1841

ADDRESS 150 N. Main, Suite 801 city/state Wichita, Ks. 67202

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684 ^{4/95}

(company name) (contractor's)
ADDRESS 150 N. Main, Ste 801, Wichita, Ks. 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (if known?) 01-18-95 . 11:30 p.m.

PAYMENT OF THE PLUGGING FEE (K.S.A. 55-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 02-13-95 AUTHORIZED OPERATOR/AGENT: Jack K. Wharton
(signature) Vice-President

ALLIED CEMENTING CO., INC.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>1-18-95</u>	SEC. <u>18</u>	TWP. <u>22</u>	RANGE <u>33</u>	CALLED OUT	ON LOCATION <u>8:15 PM</u>	JOB START <u>8:30 PM</u>	JOB FINISH <u>11:30 PM</u>
LEASE <u>Garden City "D"</u>	WELL # <u>1-18</u>	LOCATION <u>Friend SW-9S-4S</u>	COUNTY <u>Finney</u>	STATE <u>Kan</u>			

OLD OR NEW (Circle one) NEW

CONTRACTOR Abercrombie R.T.D #4

TYPE OF JOB PTA

HOLE SIZE 7 7/8 T.D. 4840'

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

OWNER Leback Oil Prod

CEMENT

AMOUNT ORDERED 345 SKs 60/40, 6 1/4" 1/4 lbs Flo-Sect

COMMON	<u>207</u>	SKs	@	<u>7.20</u>	<u>1,490.40</u>
POZMIX	<u>138</u>	SKs	@	<u>3.15</u>	<u>434.70</u>
GEL	<u>18</u>	SKs	@	<u>9.50</u>	<u>171.00</u>
CHLORIDE			@		
<u>Flo-Sect</u>	<u>86</u>	<u>SKs</u>	@	<u>1.14</u>	<u>98.90</u>
			@		
			@		
			@		
			@		
			@		
HANDLING	<u>345</u>	SKs	@	<u>1.05</u>	<u>362.25</u>
MILEAGE	<u>4¢</u>	<u>per SK/mile</u>			<u>786.60</u>

EQUIPMENT

PUMP TRUCK CEMENTER Walt

191 HELPER Wayne

BULK TRUCK DRIVER Jason

303 DRIVER _____

BULK TRUCK DRIVER _____

_____ DRIVER _____

TOTAL 3,343.85

REMARKS:

100 SKs @ 3500'

50 SKs @ 2005'

80 SKs @ 1100'

40 SKs @ 600'

50 SKs @ 290'

10 SKs @ 40'

15 SKs in pit

Hub Co

SERVICE

DEPTH OF JOB	<u>3500'</u>			
PUMP TRUCK CHARGE				<u>550.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>59 miles</u>	@	<u>2.35</u>	<u>133.95</u>
PLUG	<u>8 5/8 D.H. Plug</u>	@		<u>23.00</u>
		@		
		@		

TOTAL 706.95

CHARGE TO: Leback Oil Prod Inc.

STREET P.O. Box 489

CITY Hays STATE Kan ZIP 67601

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL _____

TAX NONE

TOTAL CHARGE 4050.80

DISCOUNT 810.16 IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Wayne Fisher

ALLIED CEMENTING CO., INC. 0000156

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT

Oakley

DATE <u>1-11-94</u>	SEC. <u>18</u>	TWP. <u>22</u>	RANGE <u>33</u>	CALLED OUT	ON LOCATION <u>8:00 PM</u>	JOB STARTS <u>9:30 PM</u>	JOB FINISH <u>10:00 PM</u>
LEASE <u>Garden City</u>	WELL # <u>1-18</u>	LOCATION <u>Friend SW-95-U.S.</u>		COUNTY <u>Finney</u>	STATE <u>Kan</u>		

OLD OR (NEW) (Circle one)

CONTRACTOR Abercrombie RTD #4
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D. 260'
 CASING SIZE 8 3/4 DEPTH 259'
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG. 15'
 PERFS.

OWNER Lebsack Oil Prod
 CEMENT

AMOUNT ORDERED 200 SKS 60/40 P&Z
3% CC - 2% Ca

EQUIPMENT
 PUMP TRUCK CEMENTER Walt
 # 300 HELPER Terry
 BULK TRUCK
 # DRIVER Dean
 BULK TRUCK
 # 218 DRIVER

COMMON @
 POZMIX @
 GEL @
 CHLORIDE @
 HANDLING @
 MILEAGE @
 TOTAL

REMARKS:

Last Cinc 2130' ran 1-Basket
80' Down, mixed 100 sks cement
on Bottom, mixed 100 sks on top
W/ 100# Halls

SERVICE

DEPTH OF JOB 260'
 PUMP TRUCK CHARGE
 EXTRA FOOTAGE @
 MILEAGE @
 PLUG @
 TOTAL

CHARGE TO: Abercrombie Drg Co Inc
 STREET
 CITY STATE ZIP

STATE COMMISSION
 FEB 16 1995

FLOAT EQUIPMENT

8 5/8
1-Basket @
 @
 @
 @
 TOTAL

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX
 TOTAL CHARGE
 DISCOUNT IF PAID IN 30 DAYS

SIGNATURE [Signature]

ALLIED CEMENTING CO., INC.

0156

PERMIT TO DRILL: BOX 31 RUSSELL, KANSAS 67665 SERVICE POINT: Oakley

DATE: <u>1-11-95</u>	SEC: <u>18</u>	TWP: <u>22</u>	RANGE: <u>33</u>	CALLED OUT	ON LOCATION: <u>8:00 PM</u>	JOB START: <u>9:30 PM</u>	JOB FINISH: <u>10:00 PM</u>
LEASE: <u>Garden City</u>				WELL #: <u>1-18</u>	LOCATION: <u>Friend SW-95-415</u>	COUNTY: <u>Finney</u>	STATE: <u>Kan</u>

OLD OR NEW (Circle one) NEW

CONTRACTOR: <u>Abercrombie RTD #4</u>	OWNER: <u>Lebsack Oil Prod</u>
TYPE OF JOB: <u>Surf Face</u>	CEMENT
HOLE SIZE: <u>12 1/4</u>	T.D.: <u>260'</u>
CASING SIZE: <u>8 7/8</u>	DEPTH: <u>259'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.: <u>15'</u>	
PERFS.	

AMOUNT ORDERED 200 sks 60/40 p02
3% cc - 2% Ca

COMMON	<u>120</u>	sk	@	<u>7.20</u>	<u>864.00</u>
POZMIX	<u>80</u>	sk	@	<u>3.15</u>	<u>252.00</u>
GEL	<u>3</u>	sk	@	<u>9.50</u>	<u>28.50</u>
CHLORIDE	<u>6</u>	sk	@	<u>28.00</u>	<u>168.00</u>
HANDLING	<u>200</u>	sk	@	<u>1.05</u>	<u>210.00</u>
MILEAGE	<u>4¢</u>	per sk/mile			<u>456.00</u>

TOTAL 1,978.50

EQUIPMENT

PUMP TRUCK	CEMENTER: <u>Walt</u>
# <u>300</u>	HELPER: <u>Terry</u>
BULK TRUCK	DRIVER: <u>Dean</u>
#	
BULK TRUCK	DRIVER
# <u>218</u>	

REMARKS:

Last Circ 2130' ran 1-Basket
80' Down, mixed 100 sk cement
on Bottom, mixed 100 sks on top
U/ 100# Hulls

SERVICE

DEPTH OF JOB	<u>260'</u>	
PUMP TRUCK CHARGE		<u>445.00</u>
EXTRA FOOTAGE	@	
MILEAGE	<u>57 mile</u>	@ <u>2.35</u> <u>133.95</u>
PLUG	<u>8 5/8 wooden Plug</u>	@ <u>45.00</u>

TOTAL 623.95

CHARGE TO: Abercrombie Drsg Co Inc

STREET: 801 Union Center

CITY: Wichita STATE: Kansas ZIP: 67202

FLOAT EQUIPMENT

<u>8 5/8</u>	
<u>40MM Basket</u>	@ <u>180.00</u>
	@
	@
	@
	@
TOTAL	<u>180.00</u>


TAX: None

TOTAL CHARGE: \$ 2,782.45

DISCOUNT: 556.49 IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE: Sho. Fisher





Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 16, 1995

Lebsack Oil Production Inc
P O Box 489
Hays KS 67601

Garden City "D" #1-18
API 15-055-21,378-0000
2310 FSL 330 FEL
Sec. 18-22S-33W
Finney County

Dear Gary Fisher,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760