

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 13 Twp. 22S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner J. Bergman Oil Company

Lease Name Teichman Well No. 1

Office Address 425 Union Center Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed July 14 19 60

Application for plugging filed July 14 19 60

Application for plugging approved July 14 19 60

Plugging commenced July 14 19 60

Plugging completed July 14 19 60

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3766 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand surface clay - shale		-0	225	8-5/8	225	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Filled hole with mud to 240 feet - set plug and hulls with 20 sacks cement through drill pipe. Filled with mud to 35 feet set plug and hills - capped to base of cellar with 10 sacks cement.

8-22-60
RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor company tools

Address _____

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Harold Bergman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman

425 Union Center Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 60

My commission expires August 2, 1962

[Signature]
Notary Public.



DRILLER'S LOG

Teichman #1
 SW SW SW Section 13-22S-13W
 Stafford County, Kansas

Date Commenced: July 1, 1960
 Date Completed: July 10, 1960
 Elevation: 1882 DF
 1885 KB

0 - 250	Sand - Surface Clay - Shale	TOPS:	
250 - 270	Shale and Shells		
270 - 725	Red Bed Shale	Anhydrite	725 (✓1160)
725 - 750	Anhydrite	Heebner Shale	3225 (-1340)
750 - 859	Shale - Red Bed	Toronto	3244 (-1359)
859 - 1480	Red Bed - Salt - Shale - Shells		
1480 - 1780	Shale and Shells	Douglas	3261 (-1376)
1780 - 1905	Shale and Lime	Brown Lime	3358 (-1473)
1905 - 2055	Lime and Shale	Lansing-Kansas City	3376 (-1491)
2055 - 2200	Lime and Shale	Base Kansas City	3598 (-1713)
2200 - 2330	Lime and Shale	Pennsylvanian Basal	
2330 - 2540	Lime and Shale	Conglomerate	3619 (-1734)
2540 - 2700	Lime and Shale	Viola	3638 (-1753)
2700 - 2875	Lime and Shale	Simpson	3695 (-1810)
2875 - 3015	Lime and Shale	Arbuckle	3755 (-1870)
3015 - 3120	Lime		
3120 - 3180	Lime and Shale		
3180 - 3274	Lime and Shale		
3274 - 3360	Lime		
3360 - 3525	Lime		
3525 - 3560	Lime		
3560 - 3600	Lime		
3600 - 3650	Lime, Cong. Chert		
3650 - 3680	Lime Cherty		
3680 - 3706	Cherty Lime - Sand		
3706 - 3720	Lime		
3720 - 3730	Lime		
3730 - 3754	Lime		
3754 - 3766	Shale and Lime		
3766	Rotary Total Depth		

RECEIVED
 STATE CORPORATION COMMISSION

AUG 22 1960

CONSERVATION DIVISION
 Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
) SS.
 county of sedgwick)

I, do swear that the statements and matter herein contained are true to the best of my knowledge.

BERGMAN DRILLING, INC.

Harold Bergman
 Harold Bergman

Subscribed and sworn to before me this 15th day of July, 1960.

My commission expires: August 2, 1962.

Norma J. Johnson
 Norma J. Johnson, Notary Public