

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford

County. Sec. 13 Twp. 22 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines

Lease Owner ~~Everett S. Graham Oil Co~~

Lease Name Schartz Well No. 1

Office Address 204 N Market, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 7/1/50 19

Application for plugging filed June 16, 1950 19

Application for plugging approved June 17, 1950 19

Plugging commenced 6/22/50 19

Plugging completed 7/1/50 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Charles Stough

Producing formation Depth to top Bottom Total Depth of Well 3668 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 1/2	260	
				5 1/2	3674	1913' 9"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom hole plug at 3500.
Set rock bridge to 3490. Run 5 sks cement.
Pumped plug to 2400.
Pumped plug to 2440.
Mudded and bailed hole. Set rock bridge at 250 to 238. Run 15 sks cement. Mudded hole to 30. Run 10 sks cement. Well complete.

RECEIVED

Conservation Div.

JUL 11 1950

STATE CORPORATION
COMMISSION
KANSAS

7-11-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. L. Graham
Address same as above

STATE OF Kansas COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of July, 1950

Virginia M. Bader
Notary Public.

My commission expires 11-16-53



WELL RECORD

SHARTZ #1

Location: CN/2 S/2 NE/4
Section 13-22-13W
Stafford County, Kansas

Commenced: March 30, 1950

Completed: April 10, 1950

Operator: William Graham Oil Company
204 North Market
Wichita, Kansas

Elevation: 1889' DF

Production:

Contractor: William Graham Oil Company
Same

Casing Record: Set 260' 8 5/8" surface pipe
Cemented same with 150 sks reg and 3 sks common cement.
Set 107 jts. 5 1/2" casing
Cemented with 50 sks regular cement.

LOG

(Figures indicate bottom of formation)

Sand and clay	210		
Shale and shells	265		
Red bed and shale	660		
Shale	790		
Shale and shells	1500		
Shale and lime	1760		
Lime	1890		<u>TOPS</u>
Lime and shale	1925		
Broken lime	1975	Lansing	3342
Lime and shale	2285	Viola	3583
Lime	2420	Sirpson	3608
Lime and shale	2470	Arbuckle	3675
Lime	2545		
Broken lime and shale	2565		
Lime and shale	2975		
Lime	3062		
Lime and shale	3170		
Lime	3319		
Lime and shale	3500		
Lime and shale	3586		
Lime	3607		
Chert and lime	3620		
Shale and Conglomerate	3640		
Shale	3677		
Arbuckle	3681		
Total Rotary Depth	3681		

RECORDED

JUN 1 1950

The undersigned, WILLIAM GRAHAM OIL COMPANY, hereby certified that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

WILLIAM GRAHAM OIL COMPANY

By J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this 13th day of April, 1950.

Virginia M. Boyle
Notary Public

My Commission Expires: 11-16-53

cc - Kansas Well Log Bureau
Lindas Oil, Inc.
George Waite

PLUGGING
FILE SEC. 13-22-13W
BOOK PAGE 11 LINE 22