

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

NORTH

**Locate well correctly on above
Section Plat**

Stafford County. Sec. 15 Twp. 22S Rge. 13. ~~E~~ (W)
Location as "NE¼NW¼SW¼" or footage from lines SE SE NE
Lease Owner Great Lakes Carbon Corporation
Lease Name Soeken Well No. 1
Office Address 501 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-8 19 49
Application for plugging filed 4-8 19 49
Application for plugging approved 4-8 19 49
Plugging commenced 4-8 19 49
Plugging completed 4-8 19 49
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production..... - - 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.....

Name of Conservation Agent who supervised plugging of this well.....Harold Hollis, Great Bend, Kansas.....
Producing formation.....None..... Depth to top.....-..... Bottom.....-..... Total Depth of Well.....3872.....Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, fromfeet tofeet for each plug set.

Hole filled with heavy mud to 300 feet
300-270 - 15 sacks cement
1270-15 - Heavy mud
15-6 Cement

RECEIVED
Conservation
APR 14 1949
STATE CORPORATION
COMMUNICATIONS
KANSAS

4-14-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Great Lakes Carbon Corporation
Address 501 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

D. H. Sholtus, Dist. Prod. Supt......(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. / / /


(Signature) M. H. J. J. J. J. Dist. Prod. Supt.

501 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1949

My commission expires.....November 8, 1950

Notary Public.



DRILLERS WELL LOG

Great Lakes Carbon Company - Soeken #1
 Commenced - 3-22-49
 Completed - 4- 9-49

DEPTH		FORMATION	REMARKS
From	To		
0	185	Sand & Gravel	
185	290	Shale & Sand streaks	
290	322	Red Bed & Shale	
322	450	Red Bed & shale	Run 11 jts of 8 5/8"
450	600	Shale & Shells	Surface, cemented with
600	710	Sand	300 sacks cement.
710	800	Shells & Shale	
800	875	Shale	
875	1240	Shale & Shells	
1240	1350	Salt & Shale	
1350	1655	Shale & Shells	
1655	1705	Shale & Shells	
1705	1790	Lime	
1790	1895	Lime	
1895	2030	Broken Lime	
2030	2150	Broken Lime & Shale	
2150	2235	Lime & Shale	
2235	2345	Lime & Shale	
2345	2424	Lime & Shale	
2424	2450	Shale & Lime	
2450	2510	Shale	
2510	2650	Shale	
2650	2745	Shale	
2745	2880	Shale	
2880	2980	Broken Lime	
2980	3070	Lime Broken	
3070	3150	Lime & Shale	
3150	3225	Lime	
3225	3265	Lime	
3265	3330	Lime	
3330	3390	Shale	
3390	3415	Lime	
3415	3470	Lime	
3470	3520	Cherty Lime	
3520	3550	Lime	
3550	3596	Lime	
3596	3645	Lime	
3645	3665	Lime & Shale	
3665	3698	Conglomerate	
3698	3710	Viola Lime	
3710	3740	Chert	
3740	3758	Chert	
3758	3765	Shale	
3765	3792	Shale & Dolomite	
3792	3797	Dolomite	
3797	3799	Cored	
3799	3807	Shale	
3807	3819	Shale	
3819	3826	Arbuckle Lime	
3826	3872	Arbuckle Lime	
3872	TD		

RECEIVED

Conservation Div.


APR 27 1949

STATE CORPORATION

PLUGGING

FILE SEC 15 T 22 R 13W

PAGE 90 LINE 44



Set plug @ 300' cemented
 with 15 sacks, set plug
 @ 25' cemented with 10
 sacks.

EXECUTED, this 11th day of April, 1949

C. L. Gabbert

STATE OF KANSAS
 COUNTY OF BARTON

} ss ACKNOWLEDGMENT FOR INDIVIDUAL

Before me, the undersigned, a Notary Public, within and for said county and State, on this 11th day of April, 1949, personally appeared C. L. Gabbert to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My commission expires April 16, 1951

Alfred L. Johnson

 NOTARY PUBLIC

new
 4-21-49