

cc: State Corporation Commission  
Mary Crump-OK City  
B. A. Conner-B'ville  
File

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 22S RGE. 13 ~~SW~~  
Location as in quarters or footage from lines:  
C SE SE SW/4

	15		

Lease Owner Phillips Petroleum Company  
Lease Name Ochel Well No. 5  
Office Address Box 287, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed 09-03-83  
Application for plugging filed 09-28-82  
Plugging commenced 10-20-82  
Plugging completed 11-01-82  
Reason for abandonment of well or producing formation Uneconomical

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
Producing formation Arbuckle Depth to top 3802' bottom 3831' T.D. 3856'  
Show depth and thickness of all water, oil and gas formations. PBID: 3837'

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0	343'	10 3/4"	334'	-0-
Production	Oil & Wtr	0	3864'	7"	3859'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. MIRU Kelso Csg Pullers and dump 18 sx sand down 7" csg to fill to 3770'. WIH w/dump bailer & dump 7 sx cmt on top of sand bridge. Pulled 16" stretch on csg min & 18" max. Shot csg @ 3314', 3113', 2917', 2713' and 2510'- did not come loose. Shot 7" @ 2308', 2104' and 1900'-came loose @ 1900'. COOH w/18 its 7", 37 its, 3 its total 57 its or 1900'. RDMO Kelso. MIRU Sun Oilwell Cmtg to 10 3/4" csg-pmpd 4 sx hulls, 30 sx 50-50 Pozmix w/3% CaCl & 2% gel, 40 sx gel & 1 sk hulls. Release wiper plug & pump 200 sx 50-50 Pozmix. ISIP-200#. To weld plate on 10 3/4" csg. Well plugged and abandoned, 11-01-82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pullers  
Chase, Kansas


STATE OF KANSAS COUNTY OF BARTON, ss.

J. R. MILLER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. R. Miller, Office Supervisor  
Box 287, Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 82

My Commission expires: February 15, 1984



Velma L. Nog  
Notary Public.

NOV 4 1982  
CONSERVATION DIVISION  
Wichita, Kansas

11-4-82