

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

NOV 12 1982

11-12-82

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 22S RGE. 13W E/W
Location as in quarters or footage from lines:
SE SE SW

Lease Owner Phillips Petroleum Company
Lease Name Ochel #5 Well No. _____
Office Address Box 287 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 10-15-82
Plugging completed 11-2-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 3856'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	343'	none
				7"	3864'	1901'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plugged off with sand to 3775' and 7 sacks cement. Shot casing @3314', 3113', 2917', 2713', 2510', 2308', 2104', 1900', pulled a total of 58 joints of 7" casing. Plugged well with 4 sacks hulls, 30 sacks cement, 40 sacks gel, 1 sack hulls, plug and 200 sacks 50/50 pos, 2% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 82



My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
Notary Public

NOV 12 1982

CONSERVATION DIVISION
Wichita, Kansas

GROUP EXPLORATION COMPANY
Sterling, Kansas

WELL LOG ----- Ochel #5
Located: C SE SE SW 1/4 Section 15-22S-13W, Stafford County, Kansas.

OWNER: Phillips Petroleum Company
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 8-25-63
COMPLETED: 9-3-63

ROTARY TOTAL DEPTH: 3865'

LOG

CASING RECORD

0 -	40	Sand, Shale & Shells
40 -	280	Sand & Gravel
280 -	700	Red Bed
700 -	1470	Shale & Shells
1470 -	1910	Shale & Lime
1910 -	2110	Lime
2110 -	2580	Shale & Lime
2580 -	2775	Lime
2775 -	2955	Lime & Shale
2955 -	3245	Lime
3245 -	3390	Shale & Lime
3390 -	3750	Lime
3750 -	3800	Shale
3800 -	3865	Lime T.D.

Set 10-3/4" Surface Casing @ 342.50' K.B. with 170 sacks common cement with 20% Diaseal D, followed with 50 sacks regular cement, 2% c.c.

Ran 7" casing @ 3864' K.B. with 20 sacks common cement with 20% Diaseal D, followed with 50 sacks common cement, salt saturated.

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1962
CONSERVATION DIVISION
Wichita, Kansas