

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 22s RGE. 13w E/W
Location as in quarters or footage from lines:
NW SE SW

Locate Well
correctly on above
Section Platt.

Lease Owner Phillips Petroleum Co.
Lease Name Ochel # M-04 Well No. _____
Office Address Box 287, Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 10/12/82
Plugging completed 10/26/82
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3868'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	354	none
				5 1/2"	3865'	2189'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2 cast iron bridge plugs set @ 3814' & 3826'. Shot casing at 3206', 3007', 2806', 2605', 2402', 2304' & 2202'. Pulled total of 68 joints of 5 1/2", Plugged well with 4 sacks hull, 20 sacks cement, 20 sacks gel 1 sack hull, 8 5/8 plug, 125 50/50 pos., 2% gel & 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1982

My Commission expires:



Irene Hoover
Notary Public.