

Original - State Corp. Comm.

Copy - B. A. Conner - 357 FPB

STATE OF KANSAS

Form CP-4

Rev. 12-15-80

Copy - Mary Crump - OK City STATE CORPORATION COMMISSION

Copy - File

200 Colorado Derby Bldg.

Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely

Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 22S RGE. 13 E/W
Location as in quarters or footage from lines:

1664' FWL & 984' ESL

Lease Owner Phillips Petroleum Company

Lease Name Ochel Well No. M04 (4)

Office Address Box 287, Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): Oil Well

Date Well Completed June 16, 1963

Application for plugging filed September 22, 1982

Plugging commenced October 12, 1982

Plugging completed October 26, 1982

Reason for abandonment of well or producing formation

Uneconomical

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Arbuckle-LKC Depth to top 3523' bottom 3808' T.D. 3868'

Show depth and thickness of all water, oil and gas formations. PBTD 3814'

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0	355'	8 5/8"	347'	-0-
Production	Oil & Water	0	3865'	5 1/2"	3860'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. 10-12-82 MIRU Kincaid WS & WTH w/2 7/8" tbg - set @ 3618'. MIRU Sun Cmtg. to 2 7/8" tbg & pmp 5 BFW, 40 sx 50-50 Pozmix, disp w/2 BFW followed by 17 bbls of 9#/gal mud. Max press 250#, Max rate - 3 BPM. LD 2 7/8" tbg. MIRU Kelso Csg Pullers and pulled 21" stretch. Shot csg @ 3206', 3007', 2806', 2605' - not loose. Shot csg @ 2304' & 2202' - came loose @ 2202'. LD 68 jts 5 1/2" csg (2202'). Cut off head. RDMO Kelso. RU Sun Cmtg. to 8 5/8" csg & pmp 4 sx hulls followed by 20 sx 50-50 Pozmix w/2% gel & 3% CaCl, followed by 20 sx gel & 1 sk hulls. Release Wiper plug & pmp 125 sx 50-50 Poz. Max press 450#, ISIP 350#. To weld plate on 8 5/8". Well P & A 10-26-82.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pullers
Chase, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer
Box 287, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 1982



My Commission expires: February 15, 1984

RECEIVED
STATE CORPORATION COMMISSION

10-27-82 OCT 27 1982

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: Phillips Petroleum Company
 CONTRACTOR: LEBEN DRILLING, INC.
 WELL: OCHEL #4
 LOCATION: 1664' FWL & 984' FSL
 Section 15-22s-13w
 Stafford County, Kansas
 COMMENCED: 6-8-63
 COMPLETED: 6-16-63

0	40	Sand & Clay
40	245	Sand, Gravel & Shale
245	357	Redbed & Shells
357	755	Redbed & Shale
755	785	Anhydrite
785	1555	Shale & Shells
1555	2600	Lime
2600	2870	Shale & Lime
2870	3225	Lime & Shale
3225	3745	Lime
3745	3795	Shale & Lime
3795	3865	Lime
	3865	Rotary Total Depth - Ran 5 7/8" new casing

Set 8 5/8" new surface casing to 355' cemented with 105 sacks common 20% Diacel "D" & 50 sacks common with 2% c.c. Cement did not circulate. Re-cemented with 125 sacks common 2% c.c. through 1" pipe.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Ochel #4, located 1664' FWL & 984' FSL of Section 15, Township 22 south, Range 13 west, Stafford County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 19th day of June, 1963.

Ulanda Nichols

 Ulanda Nichols - Notary Public

My Commission Expires: April 1, 1967