

15-185-01399-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 23 Twp. 23 Rge. (E) 13 (W)

Location as "NE/CNWxSWx" or footage from lines SE NE SE

Lease Owner SANTA-FE PIPE & SUPPLY, INC.

Lease Name SODEN Well No. 1

Office Address P. O. BOX 562, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) WASHDOWN

Date well completed 19

Application for plugging filed MARCH 22 19 66

Application for plugging approved MARCH 25 19 66


Plugging commenced MARCH 23 19 66

Plugging completed MARCH 28 19 66

Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING

Producing formation Depth to top Bottom Total Depth of Well 3800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	265'	NONE
				4 1/2"	3800'	3224.69'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3800' - 3600' - SAND
 3600' - 3564' - 3 SACKS CEMENT
 3564' - 255' - MUD
 255' - 245' - ROCK BRIDGE
 245' - 227' - 6 SACKS CEMENT
 227' - 170' - 19 SACKS CEMENT
 170' - 40' - MUD
 40' - 30' - ROCK BRIDGE
 30' - BASE - 10 SACKS CEMENT

5-16-66
RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1966

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: SANTA-FE PIPE & SUPPLY, INC.
Address: P. O. BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. L. Nutt*

P. O. BOX 562, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 27TH day of APRIL 19 66

My commission expires JULY 31, 1966 *Mary M. Sweeney* Notary Public.

API # 15-185-01529-0001


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THUNDERBIRD DRILLING, INC.
Farm- Soden No. 1

SEC. 23 T. 23 R. 13
SE NE SE

Total Depth. 3927'
Comm. 3-11-64 Comp. 3-21-64
Shot or Treated.
Contractor. Company Tools
Issued. 6-13-64

County Stafford
KANSAS



CASINO:

3 5/8" 265' cem w/250 sx.

Elevation. 1883' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand	190
shale	230
redbed	730
Anhydrite	750
shale & shells	1715
shale & lime	1920
lime & shale	2035
shale & lime	2260
lime & shale	2450
shale & lime	3183
lime & shale	3305
shale & lime	3430
lime & shale	3500
lime	3635
lime & shale	3685
lime	3775
chert & shale	3835
lime & chert	3855
shale & lime	3900
lime	3927 RTD
Total Depth	

TOPS: LOG

Anhydrite (sample)	730
Heebner	3285
Brown Lime	3424
Lansing	3450
Conglomerate	3764
Simpson Shale	3861
Simpson Dolomite	3866
Simpson Sand	3885
Arbuckle	3918

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1966
CONSERVATION DIVISION
Wichita, Kansas