


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-185-00249-0000

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 25 Twp. 23 Rge. 13 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SW, SW, SW
Lease Owner HUDSON OIL COMPANY
Lease Name SELFRIDGE
Office Address 1112 SOUTHWEST BLVD., KANSAS CITY, KANSAS Well No. 1
Character of Well (completed as Oil, Gas or Dry Hole) DRY ROTARY
Date well completed December 5, 19 58
Application for plugging filed December 5, 19 58
Application for plugging approved December 5, 19 58
Plugging commenced December 5, 19 58
Plugging completed December 5, 19 58
Reason for abandonment of well or producing formation No productible zone.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4015 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gunned up pits forming heavy mud, started laying down drill pipe filling hole up to 250'. Placed 1/4 sx. hulls, wooden plug and pushed same to 250', capped with 20 sx. cement.
Filled hole up to 40' with heavy mud, pushed 1/4 sx. hulls and wooden plug to that depth, capped with 10 sx. cement up to base of well cellar.

12-11-58

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
VERNE A. MORRIS (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris.
ROUTE #2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 8 Xkth day of XMKY December, 19 58

My commission expires July 11, 1960 Notary Public.

PLUGGING
FILE SEC. 25 T. 23 R. 13 W
BOOK PAGE 3 LINE 20

WELL LOG

15-185-00249-0000

COMPANY HUDSON OIL COMPANY

SEC. 25 T. 23S R. 13W

FARM SELFRIDGE

NO. 1

LOC. SW, SW, SW

TOTAL DEPTH 4015'


COUNTY STAFFORD CO., KANSAS

COMM. November 26, 1958

COMP. December 5, 1958

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8 5/8" @ 261' W/225 sax.



ELEVATION 1888' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

185	Clay & sand
261	Shale
745	Red bed & shells
750	Anhydrite
1475	Red bed & shale
1650	Shale
1840	Shale & lime
2135	Lime & shale
2385	Shale & lime
2790	Shale
2990	Shale & sand
3140	Shale & lime
3220	Lime & shale
3400	Shale & lime
3590	Lime & shale
3700	Lime
3779	Lime & shale
3890	Lime & chert
3940	Shale & Sand
4015	Lime
4015	T. D.

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC. 25 T. 23 R. 13W
BOOK PAGE 3 LINE 20

State of KANSAS

County of BARTON

ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 SELFRIDGE well

Subscribed and sworn to before me this 19th day of December 19 58

My Commission Expires: November 12, 1962

Verne A. Morris
NOTARY PUBLIC