


15-185-11413-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 27 Twp. 23 Rge. (E) 13W(W)  
Location as "NE/CNW/SW" or footage from lines NW SW SW  
Lease Owner MORRIS GARVIN  
Lease Name NORRIS Well No. 1  
Office Address ST. JOHN, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) SWD  
Date well completed 19  
Application for plugging filed SEPTEMBER 6 19 66  
Application for plugging approved 19  
Plugging commenced SEPTEMBER 6 19 66  
Plugging completed OCTOBER 18 19 66  
Reason for abandonment of well or producing formation LEASE ABANDONED



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING  
Producing formation Depth to top Bottom Total Depth of Well 4000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	258'	NONE
				5 1/2"	3936'	45'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4000' - 600' - 10 SACKS MUD  
600' - 35' - 75 SACKS CEMENT  
35' - 30' - ROCK BRIDGE  
30' - BASE - 10 SACKS CEMENT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 28 1966  
10-28-66

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.  
Address P. O. BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T. L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
BOX 562 - GREAT BEND, KANSAS (Address)

Subscribed and Sworn to before me this 25th day of October, 1966

[Signature] Mary M. Guesnier Notary Public.

My commission expires July 31, 1970

15-185-11413-0001

COPY


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg. Wichita, Kansas

Company - ATLANTIC REFG. CO.  
Farm - Norris No. 1.

SEC. 27 T. 23 R. 13 W  
NW SW SW

DEEPENING RECORD

Total Depth. 4000  
Comm. 9-28-44 Comp. 11-4-44  
Shot or Treated.  
Contractor. Campbell & Kuhn  
Issued. 10-6-49

County. Stafford  
KANSAS  


CASING:  
8 5/8" 258' Cem.  
5 1/2" 3936' Cem.

Elevation. 1896 DE  
Production. Dry

Figures indicate Bottom of Formations.

sand & clay 0-75  
sand 130  
red bed & clay 243  
red bed 772  
anhydrite 805  
shale 1255  
salt & shale 1380  
shale & lime 1705  
anhydrite 1775  
shale & lime 1840  
lime 1859  
shale & lime 1980  
sand 2040  
lime sdy 2078  
shale & lime 3130  
lime 3189  
lime & shale 3193  
lime 3207  
shale & lime 3431  
shale 3497  
lime & shale 3550  
lime 3681  
lime & shale 3725  
lime 3781  
shale & lime 3806  
shale 3836  
Viola lime 3858  
cherty congl 3878  
lime & chert 3898  
shale & lime 3910  
shale & sand w/strks  
of shale green 3923  
shale 3931  
shale & congl 3937  
Total Depth

Production - Dry  
(Tested rainbow show only)

Tops:  
Lansing 3496  
Viola 3836  
Simp. 3881  
Ord. Congl. 3934  
Arbuckle 3935

Deepening Record  
By Standard  
Comm. 3-19-45  
Comp. 3-23-46  
Prod. S.C.

Measurements from D.F.  
D. D. depth 3920  
cem. 3940  
lime 3973  
shale 3975  
shale & lime 3985  
lime 4000  
Total Depth

Testin:  
Input test indicated  
capacity 750 b'ls per 24 hrs

P.B. 3928

Acidized w/500 gals.  
Reacidized w/1000 gals.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 7 1966

CONSERVATION DIVISION  
Wichita, Kansas

Herman Justice  
HA-2-3897

RECEIVED

SEP 1 1966

Santa Fe Pipe & Supply

350'  
35-cks

Mud 10 cks  
Cem. 75 cks

Justice  
Nickerson