

15-185-30064-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 27 Twp. 23 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines Center S/2 SW SW

Lease Owner Northeastern Petroleum Company, Inc

Lease Name Davidson #1 Well No. 1

Office Address P. O. Box 831, Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed May 22, 1965 19

Application for plugging filed May 22, 1965 19

Application for plugging approved May 22, 1965 19


Plugging commenced May 22, 1965 19

Plugging completed May 22, 1965 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well A. Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug in bottom of hole

Filled hole with rotary mud to 235'

Cemented with 28 sacks of cement - placed plug

Filled hole with rotary mud to 40 feet

Cemented with 10 sacks of cement to top of cellar

Put 2 sacks of cement in rat hole

RECEIVED  
STATE CORPORATION COMMISSION

MAY 26 1965

5-26-65  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Northeastern Petroleum Company, Inc

Address

STATE OF Kansas, COUNTY OF Reno, ss.

Robert J. Dutton (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the

above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert J. Dutton

P. O. Box 831, Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of May, 1965

My commission expires March 4, 1969

M. L. Bowers  
Notary Public.

15-185-30064-0000

DAVIDSON #1  
Stafford County, Kansas  
Date Commenced - May 10, 1965  
Date Completed - May 22, 1965  
Drilling Contractor - Northeastern Petroleum Company, Inc  
Company - Northeastern Petroleum Company, Inc

---

0	to	275	Sand clay - Shale Shells
275	to	745	Shale, Red Bed - Shells
745	to	765	Red Bed
765	to	795	Anhydrite
795	to	1050	Shale
1050	to	1465	Shale and shells
1465	to	1930	Lime and shale
1930	to	2240	Lime
2240	to	2905	Lime and Shale
2905	to	3090	Lime
3090	to	3555	Lime and Shale
3555	to	3835	Lime
3835	to	3875	Lime and Chert (viola)
3875	to	3935	Simpson. Total Depth

Set surface casing at 273'

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1965  
CONSERVATION DIVISION  
Wichita, Kansas