

REC'D JUN 20 1968


15-185-01443-0001  
Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Stafford County, Sec. 27 Twp. 23S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NW SW NE

Lease Owner High Plains Production Company

Lease Name Lutz Well No. 1

Office Address 304 Insurance Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed ~~XANXSEE~~ January 19 68

Application for plugging filed May 29 19 68

Application for plugging approved June 3 19 68

Plugging commenced 6-3- 19 68

Plugging completed 6-8- 19 68

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production May 19 68

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren

Producing formation Simpson Depth to top 3872 Bottom 3939 Total Depth of Well 3939 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT     | FROM | TO   | SIZE  | PUT IN | PULLED OUT |
|-----------|-------------|------|------|-------|--------|------------|
| Simpson   | Oil & Water | 3872 | 3939 | 5 1/2 | 3937   | 1823       |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Push plug to 3650 ft. - sand back to 3625 - dump 5 sax cement.  
Pull 1823 ft. 5 1/2" pipe - Howco pumped 10 sax gel & 100 sax cement @ 350 lbs pressure.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 24 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
6-24-68

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc. Permit # 490

Address 320 N. Park Stafford, Kansas 67578

STATE OF Kansas COUNTY OF Sedgwick ss.  
R. W. Watchous (partner) (employee of owner or owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. W. Watchous  
R. W. Watchous  
304 Insurance Building, Wichita, Kansas 67202  
(Address)



SUBSCRIBED AND SWORN to before me this 21st day of June, 19 68

Betty Patterson  
Betty Patterson Notary Public.

My commission expires May 22, 1971

DRILLERS LOG

15-185-01443-0001  
File  
J. T. White  
J. T. White

Lutz No. 1

CASING RECORD: 8 5/8" @ 300' w/275 sx cement  
 5 1/2" @ 3938 1/2' w/100 sx cement

COMPANY: Hinkle Oil Company  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: January 16, 1963  
 COMPLETED: January 26, 1963

DESCRIPTION: NW SW NE  
 27-23S-13W  
 Stafford Co.  
 Kansas

ELEVATION:

TOTAL DEPTH: 3939'

| <u>FORMATION</u>    | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|---------------------|-------------|-----------|----------------|
| Sand                | 0           | 110       |                |
| Shale & Shells      | 110         | 220       |                |
| Sand                | 220         | 260       |                |
| Shale & Shells      | 260         | 301       |                |
| Red Bed & Shells    | 301         | 680       |                |
| Red Bed & Shale     | 680         | 740       |                |
| Anhydrite           | 740         | 780       |                |
| Shale & Shells      | 780         | 1630      |                |
| Shale & Lime        | 1630        | 3565      |                |
| Lime                | 3565        | 3755      |                |
| Lime & Chert        | 3755        | 3860      |                |
| Cherty Lime & Shale | 3860        | 3895      |                |
| Lime & Shale        | 3895        | 3939      |                |

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 3 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
 George A. Angle

Subscribed and sworn to before me this 30th day of January, 1963.

Daphne V. Head  
 Notary Public

My Commission Expires:  
11-17-66