

Original - State Corp. Comm.
Copy - B. A. Conner - 357 FPB
Copy - Mary Crump - OK City
Copy - File

15-185-11216-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 22S RGE. 13 E/W
Location as in quarters or footage from lines:
330' ENL & 330' EEL of SW/4

Lease Owner Phillips Petroleum Company
Lease Name Ochel Well No. 1
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed September 19, 1947
Application for plugging filed September 15, 1982
Plugging commenced September 30, 1982
Plugging completed October 26, 1982
Reason for abandonment of well or producing formation Uneconomical

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation Arbuckle-LKC Depth to top 3406' bottom 3815' T.D. 3815'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	442'	8 5/8"	436'	-0-
Production	Oil & Water	0'	3792'	5 1/2"	3812'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. 9-30-82 MIRU Kincaid WS, LDR&T. GIH w/2 7/8" tbg and set @ 3618'. MIRU Hallib. to 2 7/8" tbg & pmp 5 BW; 50 sx 50-50 Pozmix w/2% gel, 3% CaCl, disp w/2 BW followed by 17 bbls 9#/gal mud. Max press 500#. Max rate 5 BPM. LD 2 7/8" tbg. RDMO Hallib. & Kincaid. MIRU Kelso Csg. Pullers & pulled 2 1/2" stretch & shot csg. @ 2400' - came loose. COOH w/79 jts 5 1/2" OD 8rd 14# csg (2400'). RU Sun Cmtg. to 8 5/8" csg. Pmp 4 sx hulls, followed by 20 sx 50-50 Pozmix, w/2% gel & 3% CaCl, followed by 20 sx gel & 1 sk hulls. Release Wiper plug & pmp 125 sx 50-50 Poz. Max press 500#. ISIP 450#. To weld plate on csg. Well P & A 10-26-82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pullers
Chase, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer
Box 287, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 1982

My Commission expires: February 15, 1984

STATE OF KANSAS
NOTARY PUBLIC

OCT 27 1982 10-27-82

CONSERVATION DIVISION
Wichita, Kansas

