

14 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Anschutz Oil Co.

Complete Address: 350 Hilton Bldg., Denver, Colorado

Lease Name Bunselmeyer Well No. # 5

Location SW SW NE Sec. 2 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3672

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co.

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 11:30AM Day 12th Month August Year 1963

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cement circulated. 3663' of 5 1/2" long string,
cemented with 100 sacks. Sanded to 3650', cemented with 5 sacks. Fluid
level was up in the hole, Plug was pushed to 270', 10' rock bridge, 5
sacks cement was mixed and put on plug through dump bailer, and let
set over night. Next morning hole was bailed down and the hole was filled
with 3 yards of ready-mix cement, to the base cellar.
3055' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/13/63

INV. NO. 7572-W