

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anschutz Oil Co. Inc.

Complete Address: Denver Hilton Bldg., Denver, Colorado

Lease Name Brunselmeyer Well No. # 6

Location NE NW NE Sec. 2 Twp. 22 Rge. 13 (E) W

County Stafford Total Depth 3696

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Central Pipe Pulling

Address: 1416 Coolidge, Great Bend, Kansas License No. 459

Operation Completed: Hour 10:30AM Day 25th Month March Year 1963

The Above well was plugged as follows:

258' of 8 5/8" surface pipe cement circulated. 3656' of 5 1/2" long string
cemented with 100 sacks. Sanded to 3645' cemented with 5 sacks. Fluid
level was 60' in hole. Set plug and 15' rock and sand bridge at 230'.
Bailed fluid down, cemented with 5 sacks, let set over night. Next morning
bailed hole down but fluid came back up in hole. Set 5 sacks cement through
bailer on top of plug let set over night. Next morning fluid bailed down
and stayed in hole O.K. Finished putting 20 sacks cement on bottom plug.
Filled hole with mud to 40' with 10 sacks cement to base cellar.

2950' of 5 1/2" pipe recovered from the hole
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ardie Elving
Well Plugging Supervisor

DATE 4/2/63

INV. NO. 6823-W