

KANSAS

15-009-21361-0900

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

JUN 20 1978  
06-20-78  
CONSERVATION DIVISION  
Wichita, KS (of this well)

Operator's Full Name S-L production Co., Inc.

Complete Address P.O. Box 101, McPherson, Kansas 67450

Lease Name Schauf Well No. B-1

Location App. C NE SE Sec. 3 Twp. 16 Rge. 12 XX (W) X

County Barton Total Depth 3333'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Art Lamb Casing & Pulling, Inc.

Address 2809 King, Hutchinson, Kansas 67501 License No. 440

Operation Completed: Hour 10:30 AM Day 17 Month 6 Year 1978

The above well was plugged as follows:

Pushed plug to 3075' and sanded back to 3050' and

5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 5 sx hulls,

25 sx mud gel, plug and 100 sx cement.

Max. pres. 1000#. Shut in pres. 300#. Plugged back to 3286'.

Recovered 2740' of 5 1/2" casing. Top perforation at 3248'.

3329' of 5 1/2" casing cemented with 60 sx cement.

246' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Duane Rankin  
Well Plugging Supervisor

DATE 6-20-78

INV. NO. 7496-W