

OR P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1972
CONSERVATION DIVISION
Wichita, Kansas
2-22-72

Operator's Full Name Morris Garvin 15-185-12772-0000

Complete Address N. Broadway St. John, Ks

Lease Name Delker Well No. 3

Location SE/SW/NE Sec. 33 Twp. 23 Rge. 13 (E) (W)

County Stafford Total Depth 3925

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Santa Fe Pipe & Supply Inc.

Address Box 562 Great Bend, Ks License No. 574

Operation Completed: Hour 9:00 AM Day 18 Month 2 Year 1972

The above well was plugged as follows:

305 ft 13" surface pipe cemented with 300 sacks. 3920 ft 5½ long
string cemented with 100 sacks. Top perf. 3895 ft. Sand back to
3650 ft, 5 sacks cement with bailer. Pulled 1680 ft 5½. Pump 3 sacks
hulls, 15 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2-22-72

INV. NO. 5207-W