

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15-185-12768-0000

LOCATION NW-SE-SE

SEC. 33 TWP. 23 RGE. 13-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Clair

Operator Crown Oil Co. Inc. Address A. Brand. Kans-

Field _____ County Stafford

Total Depth 3943 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 390 ft. Circulated with cement
5 1/2" casing set at 3938 ft. Cemented with 100 sacks cement.
Plugged back to 3930 ft. with chat - Pumped
4 sacks of cement at 3930 ft. Shot off & pulled
the 5 1/2" casing - Filled hole with mud - Pumped
in Plug & 100 sacks of cement - Filling hole
from 390 ft to the surface with cement.
Sun Oil Well Cementing Co.

5-2-51

PLUGGING
FILE SEC. 33 T. 23 R. 13W
BOOK PAGE 79 LINE 13

RECEIVED C. M. Stough
District Conservation Agent
MAY 2 - Date 4-30-51
CONSERVATION DIVISION
Wichita, Kansas