



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

March 12, 1963

CONSERVATION DIVISION
WICHITA, KANSAS

3-22-63

Dear Sir:

Mr. Albert Schiffner of Forbes Caseing Pulling Co. has this
 date requested permission to plug the following described well:

Mr. Albert Schiffner guarantees payment of the plugging fee.

Operator's full Name: Forbes Caseing Pulling Co.

Complete Address: Box 221 Great Bend, Kansas.

Lease Name: Batman #8 Well No. #8

Location: NE-NW-SE Sec. 2 Twp. 22 Rge. 13 (E) (W) X

County Stafford Total Depth 3678 ^{Abandoned} Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Schiffner was instructed to plug the well as follows:

3673' of 4 1/2" long string sanded to 3660' & 3 sacks cement.
3263' pulled. 324' of surface pipe circulated with cement.
Hole filled to 200' with mud, 10' rock bridge and 25 sacks
cement. Hole filled to 40' with mud, 10' rock bridge and
10 sacks cement to base of cellar.

Very truly yours,

Herman J. Matus
 Conservation Division Agent