

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-185-10888-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1963

CONSERVATION DIVISION
Wichita, Kansas

8-1363

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Anschutz Oil Co.

Complete Address: 350 Hilton Bldg., Denver, Colorado

Lease Name: Bunselmeyer Well No. # 5

Location: SW SW NE Sec. 2 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3672 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

278' of 8 5/8" surface pipe, cement circulated. 3663' of
5 1/2" long string, cemented with 100 sacks. Sand to 3650',
cement with 5 sacks. Fill hole with mud to 270', 10' rock
bridge, cement with 20 sacks. Fill hole with mud to 40',
10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent