

State of Kansas



FORM - CP-2
15-185-10889-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

4-1-63

CONSERVATION DIVISION

WICHITA, KANSAS

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Perry Daniels of Central Pipe Pulling has this date requested permission to plug the following described well:

Mr. Daniels guarantees payment of the plugging fee.

Operator's full Name: Anschutz Oil Co. Inc.

Complete Address: Denver Hilton Bldg., Denver, Colorado

Lease Name: Brunselmeyer Well No. # 6

Location: NE NW NE Sec. 2 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3696 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Daniels was instructed to plug the well as follows:

258' of 8 5/8" surface pipe cement circulated. 3656' of
5 1/2" long string cemented with 100 sacks. Sand to 3645'
cement with 5 sacks. Fill hole with mud to 200' and 10'
rock bridge cement with 20 sacks. Fill hole with mud to
40' and 10' rock bridge cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent