

State of Kansas



15-009-011207-0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 11 1963  
09-11-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Calvin Roberts of Leben Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Herman George Kaiser guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis

Complete Address: 909 Palace Bldg., Tulsa 3, Oklahoma

Lease Name: Weber Well No. # 1

Location: NE NW NW Sec. 3 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3355 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Calvin Roberts was instructed to plug the well as follows:

8 5/8" 311' Cwc.

Filled hole with heavy mud to 300'; set plug with 1/4  
sx hulls; displaced 25 sx cement thru drill pipe. Mud to  
40'; 1/2 sx hulls; plug; displaced 12 sx cement, cementing  
to base of cellar.

Very truly yours,

Don Thomas  
Conservation Division Agent