

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

NOV 24 1965  
11-24-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Kirby Petroleum Company  
Complete Address: 402 First National Bank Bldg., Pawhuska, Oklahoma  
Lease Name Gates Well No. # A-3  
Location NW NW NE Sec. 4 Twp. 22 Rge. 13 (E) (W) W  
County Stafford Total Depth 3758'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: Strata Drilling, Inc.  
Address: 2421 Tenth St., Great Bend, Kansas License No.       
Operation Completed: Hour 10:15PM Day 21st Month Nov. Year 1965

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cement circulated with 285 sacks. Fluid  
level in the hole was at 80'. 1st cementing plug and 1 sack of hulls was  
pushed in fluid to 260', and cemented with 25 sacks, through the drill  
pipe. Hole was filled with drilling mud to 40', bridged solid with dry  
cement and hulls on fluid at 40', and cemented with 10 sacks to the base  
of the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-29-65

INV. NO. 7267-W

Signed: Archie Elving  
Well Plugging Supervisor